(*i*) That for any breach of any of the conditions of the contract by the contractor or his agents, the contract shall be void at the option of the District Forest Officer and that the latter may, after issuing to the contractor a notice of cancellation of contract, enforce forfeiture of all or any part of the deposit and shall rest the right or work it departmentally at the risk of the contractor as noted in clause (2) *supra*. If the deposit or part thereof is so forfeited, it shall be immediately made good by the contractor.

(*j*) Interest will be charged at 9 per cent per annum on all over due payment.

C. ABDUL JABBAR,
District Forest Officer.

BHADRAVATI DIVISION.

Abstract Notification dated the 16th April 1932.

The attention of the public is invited to the detailed notification of timber sale, of date *re* the sale of timber from Tarikere, Bhadravati, Channagiri and Ubrani Depots published on pages 388 and 389, Part VI of the *Mysore Gazette*, dated 21st April 1932.

H. V. RANGASWAMIENGAR,
District Forest Officer.

CHITALDRUG DISTRICT.

Abstract Notification dated 8th April 1932.

The attention of intending purchasers is drawn to pages 366 and 367, Part VI of the *Mysore Gazette*, dated 14th April 1932, notifying the sale of Honge leaves and seeds for 1932-33 to end of 33-34 in the Chitaldrug District.

Abstract Notification dated 8th April 1932.

The attention of intending purchasers is drawn to pages 356 and 357, Part VI of the *Mysore Gazette*, dated 14th April 1932, notifying the sale of Tupra leaves for 1932-33 to end of 34-35 in the Chitaldrug District.

Abstraction Notification dated 18th April 1932.

The attention of the intending purchasers is drawn to page 393, Part VI of the *Mysore Gazette*, dated 21st April 1932, notifying the resale of Thangadi and Kakke barks of several units of the Chitaldrug District for 1931-33.

B. N. IYENGAR,
District Forest Officer.

ENGINEERING DEPARTMENT.

OFFICE OF THE EXECUTIVE ENGINEER, NEW BANGALORE WATER WORKS DIVISION, THIPPAGONDANAHALLI.

NOTICE.

Notice is hereby given that sealed tenders for the supply of best hydraulic kankar wil be received up to 14th May 1932, at the Office of the Executive Engineer, New Bangalore Water Works Division, Thippagondanahalli.

2. The supply which will approximately be 5000 C.yds. but not guaranteed will be spread over a period of five months from the date of acceptance of the tenders and the monthly supply should not fall short of 1000 C.yds. in any month. The progress of supply shall be reckoned 15 days after the date of agreement.

3. The kankar shall be quarried from recognised lime stone quarries in Seringapatam and Mandya Taluks of Mysore District or other equally good kankar lime quarries.

4. The rate per C.yd. which should be written in both words and figures should be for delivery at site in stacks and should cover charges for quarrying, collecting, carting and loading into railway waggons, freight charges to Bangalore City Railway Station and delivery at site including payment of royalty and toll charges enroute.

5. The kankar brought to site shall be formed into uniform heaps in the places allotted, each measuring 10 x 3 x 1 yards or lengths in multiples of 15' or 5 yards.

6. The kankar will be examined carefully at the site by the officer in charge of the works and all bad stuff rejected and removed at the contractor's cost.

7. The measurements passed by the officer in charge shall be verified by the Executive Engineer who shall make any deduction necessary for dust or inferior stones which may vary from 8 to 15 per cent.

8. Each tender which should be sealed and superscribed "Tender for supply of kankar" should be accompanied by an earnest money of Rs. 1,000 in cash or Government Pronotes.

9. The final acceptance of the tender will rest with the Chief Engineer who does not bind himself either to accept in full or part or reject any or all tenders.

10. The acceptance of the tenders will be notified at the Office of the Executive Engineer and no replies will be given to enquiries regarding the acceptance or rejection of any tenders.

11. The earnest money of the unaccepted tenders will be returned to the parties in due time.

12. Within eight days of the acceptance of the tenders, the successful competitor will be required to enter into an agreement with the Department, in default of which, his tender will be considered cancelled and his earnest money will be forfeited to Government.

N. LAKSHMINARASIMHAIYA,
Executive Engineer,
New Bangalore Water Works Division.

TUMKUR DISTRICT.

Abstract Notification dated 9th April 1932.

Subject.—Restoring Bukkapatna Nagenhalli Minor Tank, R. No. 163 of Koratagere Taluk.

Attention of the public is drawn to notification calling for tenders for the above work in pages 374 and 375 of Part VI of the *Mysore Gazette*, dated 14th April 1932.

2. The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, up to 3 P.M. of 9th May 1932.

3. An earnest money of Rs. 400 should accompany the tender.

Abstract Notification dated 9thApril 1932.

Subject.—Restoring Kenchanahalli Minor Tank in Chitnahalli Hobli, Gubbi Taluk.

Attention of the public is drawn to notification calling for tenders for the above work in pages 375 and 376 of Part VI of the *Mysore Gazette*, dated 14th April 1932.

2. The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur up to 3 P.M. of 7th May 1932.

3. An earnest money of Rs. 400 should accompany the tender.

A. TANDONI RAO,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING.

Notification dated 20th April 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Sanitary Engineer, Bureau of Sanitary Engineering, up to 2-30 P.M., on 11th May 1932, for "Laying the Distribution System of Tiptur Water Supply." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Sanitary Engineer's Office between the hours of 11 A.M. to 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes as earnest money and be superscribed "Tender for Laying the Distribution System of Tiptur Water Supply" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Rockefeller Foundation Sanitary Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tender will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Sanitary Engineer will be final and legally binding.

Abstract estimate of quantities of work to be done for laying the Distribution System.

No.	Items of work	Per	Quantity
1	Earthwork excavation and refilling in ordinary gravelly soil with watering and tamping and reforming road surface ...	C.yd.	317
2	Laying and jointing 4″ cast iron pipes 9′ to 12′ long with lead or flange joints (all the materials being supplied by the contractor)	Joint	15
3	Laying and jointing 4″ cast iron pipes with cement ...	,,	90
4	Do 3″ pipes 9′—12′ long with lead or flange joints	,,	25
5	Laying and jointing 3″ pipes with cement joints	,,	90
6	Do galvanised iron pipes with cutting, threading, fixing specials, etc., including earthwork excavation 1½′ wide and of 2′ average depth and refilling trench with watering and tamping and reforming road surface.— ...		
	(*a*) 2″ galvanised iron pipes	R.ft.	1,865
	(*b*) 1½″ do	,,	3,041
	(*c*) 1″ do	,,	2,565
	(*d*) ¾″ do	,,	1,020
7	Constructing valve cisterns or gland cock cisterns 1′ x 1′ covering them with a slab and fixing cast iron covers in concrete as per type design	No.	61
8	Constructing Public Fountains.—		
	(*a*) Earthwork excavation	C.yd.	34
	(*b*) Laying concrete with burnt stone jelly and surki concrete.	C.ft.	204
	(*c*) Burnt stone slabs 3″ to 4″ thick, two lines dressed and fixed in mortar	S.ft.	816
	(*d*) Burnt stone slabs 6″ thick 1′ x 1′, 2 lines dressed with edges champhered, a dish cut in the centre and fixed in cement mortar	No.	34
	(*e*) Rounding the edge of edge slabs	R.ft.	476
	(*f*) Pointing with cement mortar	S.qr.	3·74
	(*g*) Cutting holes 4″ to 5″ diameter in slabs	No.	68
	(*h*) Fixing a cast iron stand in concrete	,,	34
	(*i*) Providing a teakwood capital 4″ diameter on the cast iron pipe stand	,,	34
	(*j*) Drilling 1″ to 1¼″ holes in cast iron pipes	,,	68

H. F. MARKER,
Executive Sanitary Engineer.